No.	Items of work	Per	Quantity
10	Flooring with 3" jelly concrete in mortar and cement plastering including cutting tiles, etc.	Sqr.	6·54
11	Coping with burnt brick in mortar including plastering, complete	R.ft.	54
12	Teakwood doors with battened shutters, etc., complete ..	S.ft.	225
13	Teakwood windows with battened shutters with iron bars, etc., complete.	,,	48
14	Teakwood ventilators with glazed shutters with iron bars, etc., complete.	,,	36
15	Silicate painting	Sqr.	5·80
16	Jungle wood wrought and put up including wood oiling ..	C.ft.	89·65
17	Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete.	Sqr.	14·98
18	Mangalore ridge tiles set in mortar	R.ft.	155
19	Teakwood eave boards including painting.	,,	235
20	Providing valleys at the commencement of office room with zinc sheets over ⅜" teak planks.	L. S.	..
21	Tarring wall plates and sides of doors, etc.	,,	...
22	Providing stone mortar and pestle	,,	...
23	Do sinks in bath and kitchen	,,	..
24	Constructing seats in latrine, etc.	,,	...
25	Providing 6" dia. chimneys for the escape of smoke in bath and kitchen.	No.	2
26	Providing 2" dia. galvanised iron pipes 2' long and providing hearths, etc.	L. S.	...
27	Providing Mangalore glass tiles ... ,, ...	No.	4
28	Constructing drain with jelly concrete foundation and brick in mortar sides and cement plastering, complete, and constructing a cistern outside to collect waste water	L. S.	...
29	Providing and fixing wall pegs with Honne wood planks 1" thick to keep things.	,,	...
30	Clearing ground, levelling sides and unforeseen works, etc. ...	,,	...

K. VENKATARAMAIYA,
Executive Engineer.

WATER SUPPLY DIVISION.

Abstract Notification dated 23rd—25th October 1930.

The attention of the public is invited to the detailed notification, calling for sealed tenders for laying 4" cast iron delivery and distribution pipes for Water Supply to the Northern Extension and Kuripalya at Tumkur published on page 1350 of Part VI of the *Mysore Gazette*, dated 30th October 1930.

The last day for the receipt of tenders is 14th November 1930.

M. NARASIMHAIYA,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, GAUGING AND UPPER CHANNELS DIVISION, MYSORE.

Notification dated 30th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Gauging and Upper Channels Division, Mysore, up to 5 P.M., on Saturday the 22nd November 1930, for the following items of work :—

(i) Supplying and fixing of teakwood planks over C. D. S. and Devaroy anicuts.
(ii) Packing joints between planks.
(iii) Supplying and fixing needle shutters for the Scouring Sluice in the body wall of Devaroy anicut.

1. An approximate estimate of quantities required is given below with the specification. The work should be completed not later than the end of January 1931. Further information required, if any, may be obtained at the Executive Engineer's Office between the hours of 11 A.M. and 5 P.M. on working days.

2. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer.